



WASHINGTON HYBRID

CERCIDIUM FLORIDUM



DASYLIRION WHEELER

DASYLIRION LONGISSIMUM



LANTANA 'NEW GOLD'



LEUCOPHYLLUM LAGMANIAE
"MINUTE CACTUS"



TECOMA HYBRID 'SIERRA APRICOT'



QUERCUS VIRGINIANA

PLANTING NOTES

PLANTING PLAN

1. PLANT QUANTITIES INDICATED IN THE PLANT LIST ARE FOR CONTRACTORS' CONVENIENCE ONLY. CONTRACTOR TO VERIFY PLANT QUANTITIES PER PLAN TO BID. CONTRACTOR TO PROVIDE AND INSTALL ALL PLANTS INDICATED PER PLANS.
2. ALL TREES WITHIN FIVE FEET OF PAVING SHALL BE INSTALLED WITH APPROVED DEEP ROOT BARRIER.
3. THE PROJECT WILL RECEIVE A DRAIN IRRIGATION SYSTEM. EACH PLANT WILL RECEIVE AN EMITTER AND EACH TREE AND PALM TWO BUBBLERS.

RECOMMENDED MINIMUM LANDSCAPE MAINTENANCE SCHEDULE

WEEKLY TASKS

- * Check all irrigation equipment and adjust / align as required.
- * Inspect all landscape areas for pests / pathogens.
- * Weed all shrub / groundcover areas as needed.
- * Remove landscape debris.
- * Repair planting walls and / or grade around plants to eliminate runoff.

DESERT MODERN
LANDSCAPE DESIGN

401 S. ELIOT ROAD #303
PALM SPRINGS, CALIFORNIA 92262
TEL: (760) 329-3141 FAX: (760) 329-3142
www.desertmoderndesign.com

REVISION
06-27-16

SCALE: 1"=30'-0"