




- NOTE 1 6 CAR STACK REQUIRED
4 CARS BEHIND MENU BOARD REQUIRED
- NOTE 2 PARKING REQUIRED: 100 SF
- NOTE 3 CG ZONE
- NOTE 4 PARKING AREAS AND THE DRIVE-THROUGH AISLE AND STRUCTURE SHALL BE SET BACK FROM THE ULTIMATE CURBFACE A MINIMUM OF 25 FEET.

- (1) TOW AWAY SIGN PER LOCAL CODES.
- (2) YARD LIGHT LIGHT FIXTURES TO BE SUPPLIED AND INSTALLED BY G.C. MAX. OVERALL HEIGHT 24".
- (3) NEW HC VAN ACCESSIBLE PARKING SPACE AND STRIPING.
- (4) GREASE INTERCEPTOR.
- (5) CONSTRUCT 6' HIGH TRASH ENCLOSURE ON 6" PCC PAD.
- (6) ACCESSIBLE PARKING SIGN.
- (7) PAINT HANDICAP SYMBOL - WHITE ON BLUE BACKGROUND.
- (8) NEW MENU BOARD, SENSOR LOOP, PRICE CONFIRMATION BOARD & CANOPY BY SIGN SUPPLIER. FOUNDATION AND ROUGH ELECTRICAL BY G.C. (4.0 AMPS).
- (9) PAINT TRAFFIC ARROWS - WHITE.
- (10) PAINT 12" HIGH LETTERS - WHITE.
- (11) LANDSCAPE AREA REFER TO LANDSCAPE DRAWINGS BY OTHERS.
- (12) GAS METER.
- (13) NEW SAFETY BOLLARD.
- (14) 2% MAX. SLOPE OUTSIDE DOOR.
- (15) 48" WIDE x 36" DETECTABLE WARNINGS.
- (16) ACCESSIBLE PATH OF TRAVEL.
- (17) ELECTRICAL MAIN SWITCH BOARD.
- (18) ONE WAY - DO NOT ENTER SIGN.
- (19) NEW CLEARANCE BAR 12" TO FRONT OF CURB.
- (20) DRIVE THRU LANE, CONCRETE G.C. PROVIDE BID ALTERNATE FOR BLACK CONCRETE.
- (21) WHEEL STOP.
- (22) PROVIDE NEW SIDEWALK
- (23) A.C. PAVING AND BASE.
- (24) EXISTING WATER METER.
- (25) NEW 9' HIGH MONUMENT SIGN.
- (26) EXISTING SIDEWALK TO REMAIN
- (27) CURB AT PLANTER. CIVIL PLANS BY OTHERS.
- (28) DEMO EXISTING SIDEWALK AND PROVIDE NEW DRIVEWAY
- (29) NEW ACCESSIBLE RAMP.
- (30) LOCATION OF ACCESSIBLE ENTRANCE SIGN.
- (31) NEW DIRECTIONAL SIGN (DRIVE-THRU).
- (32) H.C. SEATING SPACE TABLE TOP NOT TO EXCEED 34" IN HEIGHT. KNEE CLEARANCE MIN. 27" H X 30" W X 19" D
- (33) SMALL CMU TRASH ENCLOSURE. INSIDE FLOOR AND WALLS OF THE TRASH DUMPSTER ENCLOSURE SHALL BE SMOOTH AND SEALED WITH AN EPOXY SEALER. TRASH BINS MUST HAVE LOCKABLE LIDS. SEE SHEET A0.5
- (34) PAINT STRIPING IN PATH OF TRAVEL.
- (35) NOT USED
- (36) NOT USED
- (37) 6" CURB AND SIDEWALK.




marks
architects

architecture
interior design
retail
restaurants
space planning
master planning
lead accredited
casp

2643 fourth ave.
san diego ca 92103
619-702-9448

71905 hwy 111 #f
rancho mirage ca 92270
760-610-5264



marks architects 2016
ALL REPORTS, PLANS AND
DOCUMENTS PREPARED BY MARKS
ARCHITECTS SHALL REMAIN THE
PROPERTY OF MARKS ARCHITECTS
AND IS INTENDED FOR USE FOR THIS
SPECIFIC PROJECT ONLY.

PLNG. DEPT. SUBMITTAL	09.29.16
△	
△	
△	
△	
△	
△	
△	
△	
△	

TACO BELL
12975 PALM DR.
DESERT HOT SPRINGS, CA



SITE PLAN
AND
INFORMATION

A0.1