

NOTES:

1. PERMANENT STRIPING, BUILT LINES, AND MARKINGS SHALL BE IN ACCORDANCE WITH THE "CALIFORNIA MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES".
2. CONSTRUCT CONCRETE SIDEWALK.
3. CONSTRUCT CONCRETE CURB LANDING
4. CONSTRUCT MODULAR ACCESSIBLE PEDESTRIAN RAMP
5. CONSTRUCT STANDARD 24" CURB & GUTTER
6. CONSTRUCT STANDARD 6" STRAIGHT FLAT CURB
7. INSTALL ACCESSIBLE PARKING SPACE
8. CONSTRUCT ADOB TRASH ENCLOSURE
9. CONSTRUCT HEAVY ASPHALT SECTION OF "A" TYPE 8 AC-20 & 4" W/OTF SEAL OVER "B" TYPE 2, CLASS B AGGREGATE BASE
10. CONSTRUCT LIGHT ASPHALT SECTION OF "A" TYPE 8 AC-20 & 4" W/OTF SEAL OVER "B" TYPE 2, CLASS B AGGREGATE BASE
11. CONSTRUCT 10" MEDIAN C.P.C. LONGITUDINAL VALLEY GUTTER
12. CONSTRUCT 10" MEDIAN DRIVEWAY APRON
13. INSTALL STREET LIGHT
14. INSTALL IRRIGATION METER & BACKFLOW PREVENTER
15. INSTALL FIRE BACKFLOW PREVENTER
16. INSTALL DOMESTIC METER & BACKFLOW PREVENTER
17. INSTALL ACCESS CONTROL PEDIESTAL
18. INSTALL 8" HUB TUBULAR STEEL OR WROUGHT IRON FENCE
19. INSTALL TUBULAR STEEL OR WROUGHT IRON FENCE
20. INSTALL FIRE ACCESS GATE
21. CONSTRUCT CONCRETE PAD FOR CO2 TANK.

